

## मध्यप्रदेश ग्रामीण सड़क विकास प्राधिकरण

(म.प्र.शासन, पंचायत एवं ग्रामीण विकास विभाग के अधीन)

(म.प्र. सोसाइटी रजिस्ट्रीकरण अधिनियम 1973 के अधीन पंजीकृत संस्था : पंजीयन क्रमांक 8746/2000)

खण्ड-2, पंचम तल, पर्यावास भवन, अरेरा हिल्स भोपाल

11950

क्र. : /22/वि-12/ग्रा.स.वि.प्रा./टी-1/465/14, भोपाल दि. : 6/06/2014

### ADDENDUM

मध्यप्रदेश ग्रामीण सड़क विकास प्राधिकरण भोपाल द्वारा जारी एसएसआर (दिनांक 26.05.2014 से लागू) के अध्याय 6 में आयटम क्रमांक 6.7 एवं 6.8 सम्मिलित करते हुए निम्नलिखित जोड़ा जा रहा है -

Item No.	Description	Unit	Rate (Rs.)
6.7	<b>Dry Lean Cement Concrete Sub- base</b> Construction of dry lean cement concrete Sub- base over a prepared sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per table 600-1, cement content not to be less than 150 kg/ cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver, compacting with 8-10 tonnes vibratory roller, finishing and curing.	cum	2548
6.8	<b>Cement Concrete Pavement</b> Construction of un-reinforced, dowel jointed at expansion and construction joint only, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M40 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, dowel bars 25mm dia and 500mm long @25cm c/c or as per design, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixtures as approved, curing of concrete slabs for 14-days,	cum	5907

उपरोक्तानुसार आयटम एसएसआर (दिनांक 26.05.2014 से लागू) में अध्याय 6 में अतिरिक्त आयटम के रूप में जोड़ा गया है। यह ADDENDUM तत्काल प्रभाव से लागू होगा।




( एम. के. गुप्ता )

प्रमुख अभियंता

म.प्र. ग्रामीण सड़क विकास प्राधिकरण  
भोपाल (म.प्र.)

प्रतिलिपि -

1. निर्देशक (तक), एनआरआरडीए, पंचम तल, एनबीसीसी टॉवर, भकाजी कॉमा प्लेस, नई दिल्ली
2. मुख्य महाप्रबंधक (समस्त), म.प्र. ग्रामीण सड़क विकास प्राधिकरण ।
3. मुख्य महाप्रबंधक (वित्त), म.प्र. ग्रामीण सड़क विकास प्राधिकरण, मुख्यालय भोपाल ।
4. वित्तीय सलाहकार, म.प्र. ग्रामीण सड़क विकास प्राधिकरण, मुख्यालय भोपाल ।
5. STA, MANIT Bhopal, Govt. Engg. College Jabalpur, GSITS Indore & MITS Gwalior को सूचनार्थ ।
6. महाप्रबंधक-तक. (समस्त), म.प्र. ग्रामीण सड़क विकास प्राधिकरण ।
7. महाप्रबंधक (समस्त), म.प्र. ग्रामीण सड़क विकास प्राधिकरण पीआईयू ..... को सूचनार्थ ।
8. प्रबंधक आईटी, म.प्र. ग्रामीण सड़क विकास प्राधिकरण मुख्यालय भोपाल की ओर प्रेषित कर लेख है कि संशोधित पत्र को [www.mprrda.com](http://www.mprrda.com) वेबसाईट पर अपलोड करें।



प्रमुख अभियंता  
म.प्र. ग्रामीण सड़क विकास प्राधिकरण  
भोपाल (म.प्र.)